

SUPPLY, INSTALLATION AND MAINTENANCE OF CCTV CAMERA FOR ICT BUILDING AND LIBRARY OF TRINCOMALEE CAMPUS OF THE EASTERN UNIVERSITY, SRI LANKA

Changes made at the pre bid meeting on 18/07/2017 at 10.00AM.

- At page no 53, in General Requirement table, no need to consider the statement “**Fiber cable, Fiber patch code and Fiber Pigtail must be same in brand**” as the constructor is going to **construct only the UTP cabling.**
- In page number 63, Annexure vii. Managed Switch 24-port (PoE), 24 ports should be Gigabit ports,

Annexure VII

L2 Managed Switch 24-Port (PoE)

Item Description	Detail Specification
Ports	24 x 10/100/1000 (PoE) Auto-MDIX + 2 x Combo Gigabit SFP (mini-GBIC) or 2 x 10/100/1000